



SCS SOIL MAPPING LEGEND	
NUMBER	SOIL MAP UNIT NAME
43	CANTON
140	CHATFIELD-HOLLIS-CANTON
447	SCITUATE-NEWFIELDS
547	WALPOLE

The Dubay Group, Inc.

136 Harvey Rd. Bldg B101
Londonderry, NH 03053
603-458-6462

Engineers
Planners
Surveyors

WETLAND NOTES

THE LIMITS OF JURISDICTIONAL WETLANDS AS SHOWN ON THIS PLAN WERE DELINEATED BY BAG LAND CONSULTANTS, INC IN DECEMBER 2015 IN ACCORDANCE WITH:

1. US ARMY CORPS OF ENGINEERS REGIONAL SUPPLEMENT TO THE CORPS OF ENGINEERS WETLAND DELINEATION MANUAL: NORTHCENTRAL AND NORTHEAST REGION, TECHNICAL REPORT ERDC/EL TR-12-1, JANUARY 2012, VERSION 2.0.
2. FIELD INDICATORS OF HYDRIC SOILS IN THE UNITED STATES, A GUIDE FOR IDENTIFYING AND DELINEATING HYDRIC SOILS, VERSION 7.0. UNITED STATES DEPARTMENT OF AGRICULTURE (2010).
3. NORTH AMERICAN DIGITAL FLORA: NATIONAL WETLAND PLANT LIST, CURRENT VERSION.

REVISIONS:

DATE: COMMENT: BY:


N BY: DSJ
KED BY: JAC
EE: APRIL 30, 2025
REF: 1"=200'
738ws


CT: ANGLEWOOD



CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH

AR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
ANCHESTER. NH 03109

ITE SPECIFIC SOILS PLAN








The Dubay Group, Inc.

136 Harvey Rd. Bldg B101
Londonderry, NH 03053
603-458-6462

Engineers
Planners
Surveyors
TheDubayGroup.com



OWNER'S SIGNATURE

DAR BUILDERS, LLC
722 EAST INDUSTRIAL PARK DRIVE, UNIT 17
MANCHESTER, NH 03109
BOOK 5800 PAGE 2566 (CORRECTIVE DEED)
BOOK 5747 PAGE 1920

APPROVED BY THE CANDIA, NH

PLANNING BOARD ON: _____

CERTIFIED BY:

General area _____

SECRETARY _____

OTHER MEMBER

OTHER MEMBER _____

OTHER MEMBER _____

APPROVED BY THE CHESTER, NH

PLANNING BOARD UN:

CERTIFIED BY

CHAIRMAN: _____


TECHNICAL PLANNING

PROJECT: **TANGLEWOOD**
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER, NH

DAR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
MANCHESTER, NH 03109

ANSWER

SUBDIVISION PLAN (SHEET B)



The Dubay Group, Inc.

136 Harvey Rd. Bldg B10
Londonderry, NH 03053
603-458-6462

Engineers
Planners
Surveyors

The diagram shows a block with three distinct parts. The top part is a rectangle labeled 'A'. Below it is a larger rectangle labeled 'B'. The bottom part is a trapezoid labeled 'C' with diagonal hatching.

N BY: DSJ
KED BY: JAC
E: APRIL 30, 2025
1"=50'
738-SUB
REF: 5800-2566


CT:
ANGLEWOOD
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH



AR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
ANCHESTER, NH 03109

1. T TITLE:

**UBDIVISION PLAN
(SHEET C)**

ECT #738 SHEET 8 of 32





CERTIFICATION:

I CERTIFY THAT THIS SURVEY AND PLAN WAS PREPARED BY ME OR THOSE UNDER MY DIRECT SUPERVISION AND THAT THIS PLAN IS THE RESULT OF A PARTIAL FIELD SURVEY MADE ON THE GROUND DURING FEBRUARY 2025 AND PLAN REFERENCE NO. 3 WITH AN ERROR OF CLOSURE OF NOT MORE THAN ONE PART IN TEN THOUSAND.

GRAPHIC SCALE

50 0 25 50 100

(IN FEET)

1 inch = 50 ft.

12/18/2025

DATE


TANGLEWOOD
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH


DAR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
MANCHESTER, NH 03109


SHEET TITLE:

TOPOGRAPHIC SUBDIVISION PLAN (SHEET A)

PROJECT #738 SHEET 10 of 32








The Dubay Group, Inc.
136 Harvey Rd. Bldg B101
Londonderry, NH 03053
603-458-6462

Engineers
Planners
Surveyors
TheDubayGroup.com



1 INCH = 120 FEET



REVISIONS:

REV:	DATE:	COMMENT:	BY:
1	7/16/25	TOWN REVIEW	SJK

DRAWN BY: SJK
CHECKED BY: DGM
DATE: APRIL 30, 2025
SCALE: 1"=120'
FILE: 738-GU
DEED REF: 5800-2566

PROJECT:

TANGLEWOOD

CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH

FOR/OWNER

DAR BUILDERS, LLC




722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
MANCHESTER, NH 03109

SHEET TITLE:

GRADING, DRAINAGE, & UTILITIES OVERVIEW PLAN








The Dubay Group, Inc.
136 Harvey Rd. Bldg B101
Londonderry, NH 03053
603-458-6462

Engineers
Planners
Surveyors
TheDubayGroup.com



1 INCH = 40 FEET



REVISIONS:

REV: DATE: COMMENT: BY:
1 7/16/25 TOWN REVIEW SJK


DRAWN BY: SJK
CHECKED BY: DGM
DATE: APRIL 30, 2025
SCALE: 1"=40'
FILE: 738-GU
DEED REF: 5800-2566

PROJECT:
TANGLEWOOD
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH
FOR/OWNER

DAR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
MANCHESTER, NH 03109

SHEET TITLE:
**GRADING,
DRAINAGE, &
UTILITIES PLAN - C**

PROJECT #738 SHEET 16 of 32



The Dubay Group, Inc.

136 Harvey Rd. Bldg B101
London, NH 03053
603-458-6462

Engineers
Planners
Surveyors



REVISIONS:


N BY: SJK
KED BY: DGM
E: APRIL 30, 2025
1"=40'
738-ROAD
REF: 5800-2566


CT:
ANGLEWOOD
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH


AR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
ANCHESTER, NH 03109


三、标题栏

ROADWAY AYOUT PLAN - B














NOTE:

1. A SWPPP REPORT NEEDS TO BE PREPARED FOR THE FEDERAL NPDES PERMIT.
2. THE RESPONSIBLE AND QUALIFIED PERSONS NEED TO BE DETERMINED PRIOR TO SUBMITTING THE NOI.
3. INSPECTION REPORTS PREPARED BY THE DEVELOPER'S REPRESENTATIVE SHALL BE KEPT ON SITE AND ALSO SHALL BE PROVIDED ELECTRONICALLY TO THE TOWN. INSPECTIONS SHALL BE COMPLETED BY A QUALIFIED INDIVIDUAL; GENERALLY A CERTIFIED SPECIALIST OR PROFESSIONAL ENGINEER.




LEGEND:

-  STABILIZED TRACKING PAD
-  CATCH BASIN PROTECTION (DANDY BAG)
-  SF - SILTATION FENCE
-  SS - SILT SOXX BARRIER
-  MB - MULCH BERM
-  BLANKET SLOPE PROTECTION
-  SOIL STOCK PILE AREA



NOTE:

1. A SWPPP REPORT NEEDS TO BE PREPARED FOR THE FEDERAL NPDES PERMIT.
2. THE RESPONSIBLE AND QUALIFIED PERSONS NEED TO BE DETERMINED PRIOR TO SUBMITTING THE NOI.
3. INSPECTION REPORTS PREPARED BY THE DEVELOPER'S REPRESENTATIVE SHALL BE KEPT ON SITE AND ALSO SHALL BE PROVIDED ELECTRONICALLY TO THE TOWN. INSPECTIONS SHALL BE COMPLETED BY A QUALIFIED INDIVIDUAL; GENERALLY A CERTIFIED SPECIALIST OR PROFESSIONAL ENGINEER.

LEGEND:


The Dubay Group, Inc.

136 Harvey Rd. Bldg B101
Londonderry, NH 03053
603-458-6462

Engineers
Planners
Surveyors
TheDubayGroup.com



1 INCH = 40 FEET



REVISIONS:

REV: DATE: COMMENT: BY:

DRAWN BY: SJK
CHECKED BY: DGM
DATE: APRIL 30, 2025
SCALE: 1"=40'
FILE: 738-EROSION
DEED REF: 5800-2566

PROJECT:
TANGLEWOOD
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH
FOR/OWNER

DAR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
MANCHESTER, NH 03109




SHEET TITLE:
**EROSION
CONTROL
PLAN - B**

PROJECT #738 SHEET 24 of 32

NOTE:

1. A SWPPP REPORT NEEDS TO BE PREPARED FOR THE FEDERAL NPDES PERMIT.
2. THE RESPONSIBLE AND QUALIFIED PERSONS NEED TO BE DETERMINED PRIOR TO SUBMITTING THE NOI.
3. INSPECTION REPORTS PREPARED BY THE DEVELOPER'S REPRESENTATIVE SHALL BE KEPT ONSITE AND ALSO SHALL BE PROVIDED ELECTRONICALLY TO THE TOWN. INSPECTIONS SHALL BE COMPLETED BY A QUALIFIED INDIVIDUAL; GENERALLY A CERTIFIED SPECIALIST OR PROFESSIONAL ENGINEER.


LEGEND:



The Dubay Group, Inc.
136 Harvey Rd. Bldg B101
Londonderry, NH 03053
603-458-6462

Engineers
Planners
Surveyors

TheDubayGroup.com



REVISIONS:

DRAWN BY: SJK
CHECKED BY: DGM
DATE: APRIL 30, 2025
SCALE: 1"=40'
LE: 738-EROSION
EED REF: 5800-2566

PROJECT: **TANGLEWOOD**
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH

DAR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
MANCHESTER, NH 03109

HEET TITLE:

EROSION CONTROL PLAN - C

CONSTRUCTION SEQUENCE

- CONTRACTOR TO NOTIFY DIG-SAFE 72-HOURS PRIOR TO COMMENCEMENT OF CONSTRUCTION
- THIS SITE WILL REQUIRE A USEPA NPDES PERMIT FOR STORMWATER DISCHARGE FOR THE SITE CONSTRUCTION SINCE THE DISTURBANCE EXCEEDS ONE ACRE. THE CONSTRUCTION SITE OPERATOR SHALL DEVELOP AND IMPLEMENT A CONSTRUCTION STORM WATER POLLUTION PREVENTION PLAN (SWPPP), WHICH SHALL REMAIN ON SITE AND MADE ACCESSIBLE TO THE PUBLIC. A COMPLETED NOTICE OF TERMINATION (NOT) SHALL BE SUBMITTED TO NPDES PERMITTING AUTHORITY WITHIN 30 DAYS AFTER EITHER OF THE FOLLOWING CONDITIONS HAVE BEEN MET: FINAL STABILIZATION HAS BEEN ACHIEVED ON ALL PORTIONS OF THE SITE FOR WHICH THE PERMITTED IS RESPONSIBLE; OR ANOTHER OPERATOR/PERMITTEE HAS ASSUMED CONTROL OVER ALL AREAS OF THE SITE THAT HAVE NOT BEEN FINALLY STABILIZED.
- PRIOR TO ANY EARTH MOVING OPERATION INSTALL PERIMETER CONTROLS, I.E. SILT FENCE AND/OR MULCH BERM AROUND THE LIMITS OF DISTURBANCE OR OTHER EROSION CONTROL DEVICE (SO AS SHOWN ON THE EROSION CONTROL PLAN).
- CONSTRUCT TEMPORARY CONSTRUCTION EXIT.
- CLEAR AND GRUB WITHIN AREAS OF DISTURBANCE UNLESS OTHERWISE NOTED.
- SEDIMENT TRAPS AND/OR BASINS SHALL BE USED AS NECESSARY TO CONTAIN RUNOFF UNTIL BASINS/PONDS ARE STABILIZED.
- REMOVE AND STOCKPILE MATERIALS AS REQUIRED. STOCKPILE SHALL BE SURROUNDED WITH AN EROSION CONTROL DEVICE TO PREVENT EROSION. STOCKPILE AREAS ARE LIMITED AND THUS MANAGEMENT OF MATERIALS WILL BE REQUIRED.
- SHAPE PROPOSED DRAINAGE PONDS, DITCHES AND/OR SWALES.
- PERFORM ROUGH SITE GRADING. INSTALL DRAINAGE SYSTEMS AND UTILITIES.
- FINISH GRADE SITE, BACKFILL ROAD SUBBASE GRAVEL IN TWO COMPAKTED LIFTS. PROVIDE TEMPORARY EROSION PROTECTION TO DITCHES AND SWALES WHERE APPLICABLE, IN THE FORM OF MULCHING, JUTE MATTING OR STONE CHECK DAMS.
- ANY PERMANENT DITCHES AND SWALES SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
- PLACE BINDER LAYER OF PAVEMENT. REINSTALL BASIN INLET PROTECTION.
- PREPARE AND STABILIZE FINAL SITE GRADING BY ADDING TOPSOIL, SEED, MULCH AND FERTILIZER.
- RAISE CATCH BASIN FRAMES TO FINAL GRADE. CONSTRUCT ASPHALT WEARING COURSE.
- REMOVE TRAPPED SEDIMENTS FROM COLLECTION DEVICES AS APPROPRIATE, AND THEN REMOVE TEMPORARY EROSION CONTROL MEASURES UPON COMPLETION OF FINAL STABILIZATION OF THE SITE.

GENERAL CONSTRUCTION NOTES

- THE TEMPORARY BMPS ASSOCIATED WITH THIS PROJECT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AND LANDOWNER, WHO WILL BE RESPONSIBLE FOR INSPECTION, OPERATION, AND MAINTENANCE.
- EROSION CONTROL PROCEDURES SHALL CONFORM TO SECTION 645 OF THE "STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION OF THE NH DOT". EROSION CONTROL SHALL BE INSTALLED DOWNHILL OF ALL AREAS WHERE WORK WILL EXPOSE UNPROTECTED SOIL TO PREVENT SEDIMENT FROM ENTERING CATCH BASINS, DRAINAGE STRUCTURES AND/OR DRAINAGEWAYS. INSTALL TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES PRIOR TO ANY EARTH MOVING OPERATIONS.
- EROSION CONTROL DEVICES SHALL BE INSTALLED WHERE REQUIRED PRIOR TO ANY ON-SITE GRADING OR DISTURBANCE OF EXISTING SURFACE MATERIAL. EROSION CONTROL MEASURES SHALL BE MAINTAINED DURING DEVELOPMENT AND SHALL BE CHECKED PERIODICALLY AND EXCESS SILT SHALL BE REMOVED.
- ALL DISTURBED AREAS WHICH ARE FINISH GRADED SHALL BE LOAMED (6" MINIMUM) AND SEEDED. SEE SEEDING AND FERTILIZER SPECIFICATION. SEE SLOPE DESIGN AND/OR LANDSCAPE PLAN FOR ADDITIONAL INFORMATION.
- ANY DISTURBED AREAS WHICH ARE TO BE LEFT TEMPORARILY, AND WHICH WILL BE REGRADED LATER SHALL BE MACHINED STRAW MULCHED AND SEDED WITH SLOPE STABILIZATION SEED MIXTURE TO PREVENT EROSION. STRAW MULCH SHALL BE APPLIED AT A RATE OF 2 TONS/ACRE.
- ALL DRAINAGE SYSTEMS (DITCHES, SWALES, DRAINAGE PONDS/BASINS, ETC.) SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM. STORMWATER FLOWS ARE NOT TO BE DIRECTED TO THESE SYSTEMS UNTIL CONTRIBUTING AREAS HAVE ALSO BEEN FULLY STABILIZED.
- CONTRACTOR SHALL PROVIDE DUST CONTROL MEASURES IN ACCORDANCE WITH NHDES, EPA & TOWN REQUIREMENTS FOR THE DURATION OF THE PROJECT. WATER FOR DUST CONTROL SHALL BE PROVIDED ON SITE. FUGITIVE DUST IS CONTROLLED IN ACCORDANCE WITH ENV-A 1000.
- ALL EROSION CONTROLS ARE TO BE INSPECTED WEEKLY AND AFTER 0.5" OR GREATER OF RAINFALL WITHIN A 24 HOUR PERIOD.
- ALL FILLS SHALL BE PLACED AND COMPAKTED TO 90% MODIFIED PROCTOR DENSITY IN LAYERS NOT EXCEEDING 18 INCHES IN THICKNESS UNLESS OTHERWISE NOTED. FILL MATERIAL SHALL BE FREE FROM STUMPS, WOOD, ROOTS, ETC. AND SHALL NOT BE PLACED ON FROZEN FOUNDATION SUBGRADE.
- SILT FENCES AND/OR SILT SOXX SHALL BE PERIODICALLY INSPECTED DURING THE LIFE OF THE PROJECT AND AFTER EACH STORM. ALL DAMAGED SILT FENCES AND/OR SILT SOXX SHALL BE REPAIRED. SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED IN A SECURE LOCATION.
- PAVED AREAS MUST BE KEPT CLEAN AT ALL TIMES.
- ALL Dewatering OPERATIONS MUST DISCHARGE DIRECTLY INTO A SEDIMENT FILTER AREA.
- THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE SHALL EXCEED 5 ACRES AT ANY ONE TIME. BEFORE DISTURBED AREAS ARE STABILIZED, ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 72 HOURS AFTER FINAL GRADING. EXPOSURE OF UNSTABILIZED SOILS SHALL BE TEMPORARILY STABILIZED AS SOON AS POSSIBLE BUT NO LATER THAN 45 DAYS OF INITIAL DISTURBANCE.
- WINTERIZATION EFFORTS FOR AREAS NOT STABILIZED BY OCT. 15TH SHALL BE MADE BY THE APPROPRIATE USE OF MATTING, BLANKETS, MULCH AND SEEDING.
- AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:
 - BASE COURSE GRAVELS HAS BEEN INSTALLED IN AREAS TO BE PAVED;
 - A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;
 - A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED; OR
 - EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.
- IF, DURING CONSTRUCTION, IT BECOMES APPARENT THAT ADDITIONAL EROSION CONTROL MEASURES ARE REQUIRED TO STOP ANY EROSION ON THE CONSTRUCTION SITE DUE TO ACTUAL SITE CONDITIONS, THE CONTRACTOR SHALL BE REQUIRED TO IMMEDIATELY INSTALL AND MAINTAIN THE NECESSARY EROSION PROTECTION.

SEEDING SPECIFICATION

- TEMPORARY SEED
 - TEMPORARY VEGETATIVE COVER SHOULD BE APPLIED WHERE EXPOSED SOIL SURFACES WILL NOT BE FINAL GRADED WITHIN 45 DAYS.
 - SEED BED PREPARATION SHALL BE IN ACCORDANCE WITH THE NHDES STORMWATER MANAGEMENT MANUAL, VOLUME 3, TEMPORARY VEGETATION SECTION.
 - SEEDING MIXTURE

MIXTURE	SPECIES	POUNDS PER ACRE	POUNDS PER 1,000 SQ. FT.
WINTER RYE	112	2.50	
OATS	80	2.00	
ANNUAL RYEGRASS	40	1.00	
PERENNIAL RYEGRASS	30	0.17	
TOTAL	262	5.67	
- SEEDING SCHEDULE
 - SPRING SEEDING USUALLY GIVES THE BEST RESULTS FOR ALL SEED MIXES OR WITH LEGUMES.
 - PERMANENT SEEDING SHOULD BE COMPLETED 45 DAYS PRIOR TO THE FIRST KILLING FROST. IF SEEDING CANNOT BE DONE WITHIN THE SPECIFIED SEEDING DATES, MULCH ACCORDING TO THE NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3, CONSTRUCTION PHASE EROSION AND SEDIMENT CONTROLS AND DELAY SEEDING UNTIL THE NEXT RECOMMENDED SEEDING PERIOD.
- ESTABLISHING A STAND OF GRASS
 - STONES AND TRASH SHOULD BE REMOVED FROM LOAMED AREAS SO AS NOT TO INTERFERE WITH THE SEEDING PROCESS.
 - WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED.
 - IF APPLICABLE, FERTILIZER AND ORGANIC SOIL AMENDMENTS SHOULD BE APPLIED DURING THE GROWING SEASON.
 - APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL, FERTILIZER MAY BE APPLIED AT THE RATE OF 600 POUNDS PER ACRE OR 13.8 POUNDS PER 1,000 SQUARE FEET OF LOW PHOSPHATE FERTILIZER (N-P205-K20) OR EQUIVALENT. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE (138 LB. PER 1,000 SQUARE FEET).
 - FERTILIZER SHOULD BE RESTRICTED TO A LOW PHOSPHATE, SLOW RELEASE NITROGEN FERTILIZER.
- SEED SHOULD BE SPREAD UNIFORMLY BY A METHOD MOST APPROPRIATE FOR THE SITE. METHODS INCLUDING HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER.
 - INOCULATE ALL LEGUME SEED WITH THE CORRECT TYPE AND AMOUNT OF INOCULANTS.
 - NORMAL SEEDING DEPTH IS FROM $\frac{1}{4}$ TO $\frac{1}{2}$ INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED 10% WHEN HYDROSEEDING.
 - WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPACKER TYPE SEEDER OR HYDROSEEDER IS USED, THE SEEDED SHOULD BE FIRMED FOLLOWING SEEDING OPERATIONS WITH A ROLLER, OR LIGHT DRAG.
 - THE GRADE "A" OF SEEDING MIXTURE SHOULD BE USED WITH THE FOLLOWING SEEDING RATES, BASED ON THE SEEDING GUIDE.

MODIFIED NEW ENGLAND WETLAND PLANTS, INC. CONSERVATION/WILDLIFE MIX			
BOTANICAL NAME	COMMON NAME	INDICATOR	% BY WEIGHT
ELYMUS VIRGINICUS	VIRGINIA WILD RYE	FACW-	32
SCHIZACHYRIUM SCOPARIUM	LITTLE BLUESTEM	FACU	28
ANDROPOGON GERARDII	BIG BLUESTEM	FAC	25
DESMODIUM CANADENSE	SHOWY TICK TREFOIL	FACU	5
ASCLEPIAS SYRIACA	COMMON MILKWEED	FACU-	5
EUPATORIUM PERfoliatum	BONESET	FACW	2
ASTER NOVAE-ANGliae	NEW ENGLAND ASTER	FACW-	2
SOLIDAGO JUNcea	EARLY GOLDENROD		1

- ALTERNATE PERMANENT SEEDING FOR AREAS NOT RECEIVING LAWN OR LANDSCAPING SHALL BE AS FOLLOWS:
 - THE NEW ENGLAND EROSION CONTROL/RESTORATION MIX CONTAINS A SELECTION OF NATIVE GRASSES AND WILDFLOWERS DESIGNED TO COLONIZE GENERALLY MOIST, RECENTLY DISTURBED SITES WHERE QUICK GROWTH OF VEGETATION IS DESIRED TO STABILIZE THE SOIL SURFACE. THIS MIX IS PARTICULARLY APPROPRIATE FOR DETENTION BASINS WHICH DO NOT NORMALLY HOLD STANDING WATER. THE PLANTS IN THIS MIX CAN TOLERATE INFREQUENT INUNDATION, BUT NOT CONSTANT FLOODING. IN NEW ENGLAND, THE BEST RESULTS ARE OBTAINED WITH A SPRING OR EARLY FALL SEEDING. SUMMER AND FALL SEEDING CAN BE SUCCESSFUL WITH A LIGHT MULCHING OF WEED-FREE STRAW TO CONSERVE MOISTURE. LATE FALL AND WINTER DORMANT SEEDING REQUIRE A SLIGHT INCREASE IN THE SEEDING RATE. FERTILIZATION IS NOT REQUIRED UNLESS THE SOILS ARE PARTICULARLY INFERTILE.
 - APPLICATION RATE: 35 LBS/ACRE 1245 SQ FT/LB
 - SPECIES: SWITCHGRASS (PANICUM VIRGATUM), CREEPING RED FESCUE (FESTUCA RUBRA), VIRGINIA WILD RYE (ELYMUS VIRGINICUS), FOX SEDGE (CAREX VULPINOIDEA), CREEPING BENTGRASS (AGROSTIS STOLONIFERA), SILKY WILD RYE (ELYMUS LILLOSOIS), NODDING BUR-MARIGOLD (BIDENS CERNUA), SOFT RUSH (JUNCUS EFFUSUS), GRASS-LEAVED GOLDENROD (SOLIDAGO GRAMINIFOLIA), SENSITIVE FERN (ONOCLEA SENSIBILIS), JOE-PYE WEED (EUPATORIUM MACULATUM), BONESET (EUPATORIUM PERfoliatum), FLAT-TOP ASTER (ASTER UMBELLATUS), NEW YORK ASTER (ASTER NOVI-BELGII), BLUE Vervain (VERBENA hastata).


WINTER NOTES

- ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING. ELSEWHERE, THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS;
- ALL AREAS TO BE PLANTED WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.
- AFTER OCTOBER 15TH, INCOMPLETE SURFACES TO BE PAVED, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NH DOT ITEM 304.3 OR CRUSHED STONE.


MAINTENANCE AND PROTECTION

- THE CONTRACTOR SHALL TAKE WHATEVER MEASURES ARE NECESSARY TO PROTECT THE GRASS WHILE IT DEVELOPS.
- TO BE ACCEPTABLE, SEDED AREAS SHALL CONSIST OF A UNIFORM STAND OF AT LEAST 90 PERCENT ESTABLISHED PERMANENT GRASS SPECIES, WITH A UNIFORM COUNT OF AT LEAST 100 PLANTS PER SQUARE FOOT.
- SEDED AREAS WILL BE FERTILIZED AND RE-SEEDED AS NECESSARY TO INSURE VEGETATIVE ESTABLISHMENT.
- THE SWALES WILL BE CHECKED WEEKLY AND REPAIRED WHEN NECESSARY, UNTIL ADEQUATE VEGETATION IS ESTABLISHED.
- THE SILT FENCE AND/OR SILT SOXX BARRIER AND ANY OTHER EROSION CONTROL DEVICE SHALL BE CHECKED AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL.
- ALL EROSION CONTROL DEVICES SHALL BE REMOVED ONCE VEGETATION IS ESTABLISHED, AND DISTURBED AREAS RESULTING FROM SILT FENCE AND/OR SILT SOXX REMOVAL SHALL BE PERMANENTLY SEEDED.

NOTE
THE STUMP GRINDINGS BERM MUST BE A MINIMUM OF 12" HIGH, AS MEASURED ON THE UPHILL SIDE OF THE BARRIER, AND A MINIMUM OF TWO FEET WIDE, PER NHDES.



MULCH BERM NOT TO SCALE




MATTING INSTALLATION NOTES

- PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER AND SEED.
- BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP X 6" WIDE TRENCH WITH APPROXIMATELY 12" OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND RECOVER REMAINING 12" PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE BLANKET.
- CONSECUTIVE BLANKETS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" OVERLAP. STAPLE THROUGH OVERLAPPED AREA APPROXIMATELY 12" APART ACROSS ENTIRE BLANKET WIDTH.
- IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.
- INSTALL PRODUCT IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.

- ROLL THE BLANKETS (A) DOWN OR (B) HORIZONTALLY ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN ON THE STAPLE PATTERN SIDE. WHEN USING OPTIMUM STAPLE PATTERN SIDE, FILTER CLOTH PROTECTION, CHECK DRAINS AND SEDIMENT TRAPS SHALL NOT CONTAIN PLASTIC, OR MULTI-FILAMENT OR MONOFILAMENT POLYPROPYLENE NETTING OR MESH WITH AN OPENING SIZE OF GREATER THAN 1/8 INCHES.
- ALL MANUFACTURED EROSION AND SEDIMENT CONTROL PRODUCTS, WITH THE EXCEPTION OF TURF REINFORCEMENT MATS, UTILIZED FOR, BUT NOT LIMITED TO, SLOPE PROTECTION, RUNOFF DIVERSION, SLOPE STABILIZATION, PERMANENT CONSTRUCTION PROTECTION, CHECK DRAINS AND SEDIMENT TRAPS SHALL NOT CONTAIN PLASTIC, OR MULTI-FILAMENT OR MONOFILAMENT POLYPROPYLENE NETTING OR MESH WITH AN OPENING SIZE OF GREATER THAN 1/8 INCHES.

SLOPE PROTECTION EROSION CONTROL MATTING

NOT TO SCALE




MAINTENANCE NOTES:

- GRASSED CHANNELS SHOULD BE INSPECTED PERIODICALLY (AT LEAST ANNUALLY) FOR SEDIMENT ACCUMULATION, EROSION, AND CONDITION OF SURFACE LINING (VEGETATION OR RIP-RAP). REPAIRS, INCLUDING STONE OR VEGETATION REPLACEMENT, SHOULD BE MADE BASED ON THIS INSPECTION.
- REMOVE SEDIMENT AND DEBRIS ANNUALLY, OR MORE FREQUENTLY AS WARRANTED BY INSPECTION.
- MOW VEGETATED CHANNELS BASED ON FREQUENCY SPECIFIED BY DESIGN. MOWING AT LEAST ONCE PER YEAR IS REQUIRED TO CONTROL ESTABLISHMENT OF WOOD VEGETATION. IT IS RECOMMENDED TO CUT GRASS NO SHORTER THAN 4 INCHES.

GRASS LINED SWALE DETAIL

NOT TO SCALE








NOTES


- FILTER CLOTH - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE SURFACE.
- WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
- MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
- WASHING - WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN STORM EVENT.

USDA-SCS STABILIZED TRACKING PAD

NOT TO SCALE








The Dubay Group, Inc.
136 Harvey Rd. Bldg B101
Londonderry, NH 03053
603-458-6462

Engineers
Planners
Surveyors
TheDubayGroup.com



REVISIONS:
REV: DATE: COMMENT: BY:
1 7/16/25 TOWN REVIEW SJK

DRAWN BY: SJK
CHECKED BY: DGM
DATE: APRIL 30, 2025
SCALE:
FILE: 738-DETAILS
DEED REF: 5800-2566


PROJECT:
TANGLEWOOD
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH
FOR/OWNER

DAR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
MANCHESTER, NH 03109


SHEET TITLE:

SITE DETAILS - D

PROJECT #738 SHEET 29 of 32



TYPICAL POND SECTION & PRINCIPLE SPILLWAY PROFILE DETAIL
NOT TO SCALE



TYPICAL POND SECTION & PRINCIPLE SPILLWAY PROFILE DETAIL
NOT TO SCALE

CONSTRUCTION CRITERIA:


- FOUNDATION PREPARATION - THE FOUNDATION AREA SHALL BE CLEARED OF TREES, LOGS, STUMPS, ROOTS, BRUSH, BOULDERS, SOD, AND RUBBISH, IF NEEDED TO ESTABLISH VEGETATION, THE TOPSOIL AND SOD SHALL BE STOCKPILED AND SPREAD ON THE COMPLETED DAM AND SPILLWAYS. FOUNDATION SURFACES SHALL BE SLOPED NO STEEPER THAN 1:1. THE FOUNDATION AREA SHALL BE THOROUGHLY SCARIFIED BEFORE PLACEMENT OF THE MATERIAL. THE SURFACE SHALL HAVE MOISTURE ADDED OR IT SHALL BE COMPAKTED IF NECESSARY SO THAT THE FIRST LAYER OF FILL MATERIAL CAN BE COMPAKTED AND BONDED TO THE FOUNDATIONS.
- THE CUTOFF TRENCH AND ANY OTHER REQUIRED EXCAVATIONS SHALL BE DUG TO THE LINES AND GRADES SHOWN ON THE PLANS OR AS STAKED IN THE FIELD. IF THEY ARE SUITABLE, EXCAVATED MATERIALS SHALL BE USED IN THE PERMANENT FILL.
- EXISTING STREAM CHANNELS IN THE FOUNDATION AREA SHALL BE SLOPED NO STEEPER THAN 1:1 AND DEEPEENED AND WIDENED AS NECESSARY TO REMOVE ALL STONES, GRAVEL, SAND, STUMPS, ROOTS, AND OTHER OBJECTIONAL MATERIAL AND TO ACCOMMODATE COMPAKTION EQUIPMENT.
- FOUNDATION AREAS SHALL BE KEPT FREE OF STANDING WATER WHEN FILL IS BEING PLACED ON THEM.
- FILL PLACEMENT - THE MATERIAL PLACED IN THE FILL SHALL BE FREE OF DETRIMENTAL AMOUNTS OF SOD, ROOTS, FROZEN SOIL, STONES MORE THAN 6 INCHES IN DIAMETER (EXCEPT FOR ROCK FILLS), AND OTHER OBJECTIONAL MATERIAL.
- SELECTED BACKFILL MATERIAL SHALL BE PLACED AROUND STRUCTURES, PIPE CONDUITS, AND ANTISEEP COLLARS AT ABOUT THE SAME RATE ON ALL SIDES TO PREVENT DAMAGE FROM UNEQUAL LOADING.
- THE PLACING AND SPREADING OF FILL MATERIAL SHALL BE STARTED AT THE LOWEST POINT OF THE FOUNDATION AND THE FILL BROUGHT UP IN HORIZONTAL LAYERS OF SUCH THICKNESS THAT THE REQUIRED COMPAKTION CAN BE OBTAINED. THE FILL SHALL BE CONSTRUCTED IN CONTINUOUS HORIZONTAL LAYERS EXCEPT WHERE OPENINGS OR SECTIONALIZED FILLS ARE REQUIRED. IN THOSE CASES, THE SLOPE OF THE BONDING SURFACES BETWEEN THE EMBANKMENT IN PLACE AND THE EMBANKMENT TO BE PLACED SHALL NOT BE STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL. THE BONDING SURFACE SHALL BE TREATED THE SAME AS THAT SPECIFIED FOR THE FOUNDATION SO AS TO INSURE A GOOD BOND WITH THE NEW FILL.
- THE DISTRIBUTION AND GRADATION OF MATERIALS SHALL BE SUCH THAT NO LENSES, POCKETS, STREAMS, OR LAYERS OF MATERIAL DIFFER SUBSTANTIALLY IN TEXTURE OR GRADATION FROM THE SURROUNDING MATERIAL. IF IT IS NECESSARY TO USE MATERIALS OF VARYING TEXTURE AND GRADATION, THE MORE IMPERVIOUS MATERIAL SHALL BE PLACED IN THE CENTER AND UPSTREAM PARTS OF THE FILL. IF ZONED FILLS OF SUBSTANTIALLY DIFFERENT MATERIALS ARE SPECIFIED, THE ZONES SHALL BE PLACED ACCORDING TO THE LINES AND GRADES SHOWN ON THE DRAWINGS. THE COMPLETE WORK SHALL CONFORM TO THE LINES, GRADES, AND ELEVATIONS SHOWN ON THE DRAWINGS OR AS STAKED IN THE FIELD.
- MOISTURE CONTROL - THE MOISTURE CONTENT OF THE FILL MATERIAL SHALL BE ADEQUATE FOR OBTAINING THE REQUIRED COMPAKTION. MATERIAL THAT IS TOO WET SHALL BE DRIED TO MEET THIS REQUIREMENT, AND MATERIAL THAT IS TOO DRY SHALL HAVE WATER ADDED AND MIXED UNTIL THE REQUIREMENT IS MET.
- COMPAKTION - CONSTRUCTION EQUIPMENT SHALL BE OPERATED OVER THE AREAS OR EACH LAYER OF FILL TO INSURE THAT THE REQUIRED COMPAKTION IS OBTAINED. SPECIAL EQUIPMENT SHALL BE USED IF NEEDED TO OBTAIN THE REQUIRED COMPAKTION.
- IF A MINIMUM REQUIRED DENSITY IS SPECIFIED, EACH LAYER OF FILL SHALL BE COMPAKTED AS NECESSARY TO OBTAIN THAT DENSITY.
- FILL ADJACENT TO STRUCTURES, PIPE CONDUITS, AND ANTISEEP COLLARS SHALL BE COMPAKTED TO A DENSITY EQUIVALENT TO THAT OF THE SURROUNDING FILL BY MEANS OF HAND TAMPING OR MANUALLY DIRECTED POWER TAMPER OR PLATE VIBRATORS. FILL ADJACENT TO CONCRETE STRUCTURES SHALL NOT BE COMPAKTED UNTIL THE CONCRETE IS STRONG ENOUGH TO SUPPORT THE LOAD.
- PROTECTION - A PROTECTIVE COVER OF VEGETATION SHALL BE ESTABLISHED ON ALL EXPOSED SURFACES OF THE EMBANKMENT, SPILLWAY, AND BORROW AREA IF SOIL AND CLIMATIC CONDITIONS PERMIT. IF SOIL OR CLIMATIC CONDITIONS PRECLUDE THE USE OF VEGETATION AND PROTECTION IS NEEDED, NON-VEGETATIVE MEANS, SUCH AS MULCHES OR GRAVEL, MAY BE USED. IN SOME PLACES, TEMPORARY VEGETATION MAY BE USED UNTIL CONDITIONS PERMIT ESTABLISHMENT OF PERMANENT VEGETATION. THE EMBANKMENT AND SPILLWAY SHALL BE FENCED IF NECESSARY TO PROTECT THE VEGETATION.
- SEEDBED PREPARATION, SEEDING, FERTILIZING, AND MULCHING SHALL COMPLY WITH THE APPROPRIATE VEGETATIVE BMPs.
- CONCRETE - THE MIX DESIGN AND TESTING OF CONCRETE SHALL BE CONSISTENT WITH THE STRENGTH REQUIREMENTS OF THE JOB. MIX REQUIREMENTS OR NECESSARY STRENGTH SHALL BE SPECIFIED. THE TYPE OF CEMENT, AIR ENTRAINMENT, SLUMP, AGGREGATE, OR OTHER PROPERTIES SHALL BE SPECIFIED IF NECESSARY. ALL CONCRETE SHALL BE CONSIST OF A WORKABLE MIX THAT CAN BE PLACED AND FINISHED IN AN ACCEPTABLE MANNER. NECESSARY CURING SHALL BE SPECIFIED. REINFORCING STEEL SHALL BE PLACED AS INDICATED ON THE PLANS AND SHALL BE HELD SECURELY IN PLACE DURING CONCRETE PLACEMENT. SUBGRADES AND FORMS SHALL BE INSTALLED TO LINE AND GRADE, AND THE FORMS SHALL BE MORTAR TIGHT AND UNYIELDING AS THE CONCRETE IS PLACED.
- DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUNOFF, WATER FROM EXCAVATIONS) TO DETENTION BASIN.
- VEGETATION SHOULD BE ESTABLISHED IMMEDIATELY.
- DO NOT PLACE SYSTEMS INTO SERVICE UNTIL CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.
- DO NOT TRAFFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION SYSTEM.
- AFTER THE INFILTRATION SYSTEM AREA IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR SHOULD BE DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW TO RESTORE INFILTRATION RATES, FOLLOWED BY A PASS WITH A LEVELING DRAG.
- DO NOT PLACE INFILTRATION SYSTEMS INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.

MAINTENANCE:

MAINTENANCE IS NECESSARY IF DETENTION/RETENTION BASINS ARE TO CONTINUE TO FUNCTION AS ORIGINALLY DESIGNED. A LOCAL GOVERNMENT, A DESIGNATED GROUP SUCH AS A HOMEOWNERS' ASSOCIATION OR SOME INDIVIDUAL MUST BE ASSIGNED RESPONSIBILITY FOR MAINTAINING THE STRUCTURES AND THE BASIN AREA. A MAINTENANCE PLAN SHOULD BE DEVELOPED THAT OUTLINES THE MAINTENANCE OPERATIONS AND A SCHEDULE FOR CARRYING OUT THE PROCEDURES.


THE FOLLOWING ARE SOME ITEMS WHICH SHOULD BE CONSIDERED IN FORMULATING A MAINTENANCE PLAN.

- EMBANKMENT - THE EMBANKMENT SHOULD BE INSPECTED ANNUALLY TO DETERMINE IF RODENT BURROWS, WET AREAS, OR EROSION OF THE FILL IS TAKING PLACE.
- VEGETATION - THE VEGETATED AREAS OF THE STRUCTURE SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED GROWTH. LIME AND FERTILIZER SHOULD BE APPLIED AS NECESSARY AS DETERMINED BY SOIL TESTS. TREES AND SHRUBS SHOULD BE KEPT OFF THE EMBANKMENT AND EMERGENCY SPILLWAY AREAS.
- INLETS - PIPE INLETS AND SPILLWAY STRUCTURES SHOULD BE INSPECTED ANNUALLY AND AFTER EVERY MAJOR STORM. ACCUMULATED DEBRIS AND SEDIMENT SHOULD BE REMOVED. IF PIPES ARE COATED, THE COATING SHOULD BE CHECKED AND REPAIRED AS NECESSARY.
- OUTLETS - PIPE OUTLETS SHOULD BE INSPECTED ANNUALLY AND AFTER EVERY MAJOR STORM. THE CONDITION OF THE PIPES SHOULD BE NOTED AND REPAIRS MADE AS NECESSARY. IF EROSION IS TAKING PLACE THEN MEASURES SHOULD BE TAKEN TO STABILIZE AND PROTECT THE AFFECTED AREA OF THE OUTLET.
- SEDIMENT - SEDIMENT SHOULD BE CONTINUALLY CHECKED IN THE BASIN. WHEN SEDIMENT ACCUMULATIONS REACH THE PREDETERMINED DESIGN ELEVATION, THEN THE SEDIMENT SHOULD BE REMOVED AND PROPERLY DISPOSED OF.
- SAFETY INSPECTIONS - ALL PERMANENT IMPOUNDMENTS SHOULD BE INSPECTED BY A QUALIFIED PROFESSIONAL ENGINEER ON A PERIODIC BASIS. IF THERE IS A POTENTIAL FOR SIGNIFICANT DAMAGE OR LOSS OF LIFE DOWNSTREAM, THEN THE INSPECTION SHOULD BE CARRIED OUT ANNUALLY. THE DESIGNATED INDIVIDUAL OR GROUP SHOULD ALSO MAKE INSPECTIONS AFTER EVERY MAJOR STORM EVENT.



The Dubay Group, Inc.
136 Harvey Rd. Bldg B101
Londonerry, NH 03053
603-458-6462

Engineers
Planners
Surveyors
TheDubayGroup.com



REVISIONS:

REV: DATE: COMMENT: BY:

DRAWN BY: SJK
CHECKED BY: DGM
DATE: APRIL 30, 2025
SCALE:
FILE: 738-DETAILS
DEED REF: 5800-2566


PROJECT:
TANGLEWOOD
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH
FOR/OWNER

DAR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
MANCHESTER, NH 03109


SHEET TITLE:

SITE DETAILS - E


PROJECT #738 SHEET 30 of 32



PLAN VIEW




SECTION A-A



SECTION B-B

OVERFLOW SPILLWAY
NOT TO SCALE



MAINTENANCE REQUIREMENTS:

1. INSPECT AT LEAST ONCE ANNUALLY FOR ACCUMULATION OF SEDIMENT AND DEBRIS AND FOR SIGNS OF EROSION WITHIN APPROACH CHANNEL, SPREADER CHANNEL OR DOWN-SLOPE OF THE SPREADER.
2. REMOVE DEBRIS WHENEVER OBSERVED DURING INSPECTION.
3. REMOVE SEDIMENT WHEN ACCUMULATION EXCEEDS 25% OF SPREADER CHANNEL DEPTH.
4. MOW AS REQUIRED BY LANDSCAPING DESIGN. AT A MINIMUM, MOW ANNUALLY TO CONTROL WOODY VEGETATION WITHIN THE SPREADER.
5. SNOW SHOULD NOT BE STORED WITHIN OR DOWN-SLOPE OF THE LEVEL SPREADER OR ITS APPROACH CHANNEL.
6. REPAIR ANY EROSION AND RE-GRADE OR REPLACE BERM MATERIAL, AS WARRANTED BY INSPECTION.
7. RECONSTRUCT THE SPREADER IF DOWN-SLOPE CHANNELIZATION INDICATES THAT THE SPREADER IS NOT LEVEL OR THAT DISCHARGE HAS BECOME CONCENTRATED, AND CORRECTIONS CANNOT BE MADE THROUGH MINOR RE-GRADING.

DESIGN PARAMETER	CRITERIA
SLOPE OF RECEIVING AREA	< 15% (ALONG FLOW PATH)
LEVEL SPREADER GUIDE	BOTTOM OF SPREADER CHANNEL, AND BASE AND TOP OF BERM SHOULD BE 0% GRADE
SPREADER CHANNEL CROSS SECTION	6-INCH DEEP TRAPEZOIDAL TROUGH
SPREADER CHANNEL BOTTOM WIDTH	≥ 3 FEET
SIDE SLOPES	2:1 OR FLATTER (LEVEL SPREADER CHANNEL AND BERM)
BERM TO WIDTH	≥ 2 FEET
BERM HEIGHT	≥ 18 INCHES
STONE GRADATION	SEE TABLE 4-13
LENGTH OF LEVEL SPREADER	WHEN PART OF A TREATMENT PRACTICE, THE LENGTH SHOULD BE AS REQUIRED FOR THAT PRACTICE. IF NOT, THE LENGTH SHOULD BE NO LESS THAN 5 FEET.


TABLE 4-13. GRADATION OF STONE FOR LEVEL SPREADER BERM

SIEVE DESIGNATION	PERCENT BY WEIGHT PASSING SQUARE MESH SIEVE
12-INCH	100%
6-INCH	84% - 100%
3-INCH	68% - 83%
1-INCH	42% - 55%
NO. 4	8% - 12%

STONE BERM LEVEL SPREADER DETAIL


NOT TO SCALE

REFERENCE: NH STORMWATER MANUAL, VOLUME 2 SECTION 4-6.2



The Dubay Group, Inc.
136 Harvey Rd. Bldg B101
Londonerry, NH 03053
603-458-6462

Engineers
Planners
Surveyors
TheDubayGroup.com






The Dubay Group, Inc.

136 Harvey Rd. Bldg B101
Londonderry, NH 03053
603-458-6462

Engineers
Planners
Surveyors
TheDubayGroup.com



REVISIONS:

REV: DATE: COMMENT: BY:

DRAWN BY: SJK
CHECKED BY: DGM
DATE: APRIL 30, 2025
SCALE:
FILE: 738-DETAILS
DEED REF: 5800-2566


PROJECT: TANGLEWOOD
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH
FOR/OWNER

DAR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
MANCHESTER, NH 03109


SHEET TITLE:

SITE DETAILS - G

PROJECT #738 SHEET 32 of 32




30,000 GAL. FIRE CISTERN TANK - SECTION B-B
N.T.S.



PLAN
N.T.S.


NOTE: ALL INTERNAL PLATES AND ALL TANK PENETRATIONS AND FITTINGS TO BE FACTORY INSTALLED.
ALL STEEL SHALL BE HOT DIPPED GALVANIZED.

30,000 GAL. FIRE CISTERN TANK
N.T.S.




DEADMAN DETAIL
N.T.S.

NOTE: MAINTAIN 3" OF COVER ON THE REBAR



PIPE SUPPORT DETAIL
N.T.S.

NOTE: ALL CAST-IN PLACE CONCRETE TO BE 4,000 P.S.I. COMPRESSIVE STRENGTH MIN.



WATER LEVEL INDICATOR
N.T.S.

SEE NOTES 6 & 7 FOR FILL REQUIREMENTS


GENERAL NOTES:

SEE ALSO CONSTRUCTION CRITERIA AND STRUCTURAL NOTES

1. SUCTION AND FILL PIPES SHALL SLOPE A 1" PER FOOT BACK TO TANK.
2. ALL STEEL PIPES TO BE ASTM SCH 40 UNLESS OTHERWISE STATED. ALL BELOW-GRADE CISTERN PIPING SHALL BE COATED WITH ONE APPLICATION OF CIM1000. ABOVE GROUND CISTERN PIPING SHOULD BE PAINTED "SAFETY RED"; BOLLARDS ARE TO BE PAINTED "SAFETY YELLOW"; BOTH SHALL BE PAINTED WITH DURA CLAD 85 RUST INHIBITIVE EPOXY PRIMER, SHERWIN WILLIAMS #6018-39384, 6.0 MILS THICK, TOPCOAT SHALL BE MACROPoxy 646 FAST CURE EPOXY, SHERWIN WILLIAMS #6012-22516, 10.0 MILS THICK, FINAL COAT SHALL BE DIAMOND-CLAD URETHANE CLEAR COAT, 4 MILS THICK SHERWIN WILLIAMS #6403-11882.
3. EXCAVATION OF LEDGE (IF NEEDED) WILL BE SLOPED TO DRAIN AND PVC DRAINS SHALL BE INSTALLED, TO PROVIDE POSITIVE DRAINAGE AROUND THE TANK AND AWAY FROM THE SITE.
4. DRAFT PIPE SHALL BE EQUIPPED WITH A 6" KOCHKE DOUBLE SWIVEL FEMALE SUCTION CONNECTION SET 26" ABOVE STREET GRADE REQUIRED.
5. A MANHOLE WITH PROVISION FOR PADLOCKING SHALL BE PROVIDED BY THE INSTALLER (SEE DETAIL). KNOX PADLOCK TYPE AS REQUIRED BY CHESTER FIRE DEPT.
6. BEDDING FOR THE CISTERN SHALL BE A MINIMUM THICKNESS OF 12" OF WASHED PEA STONE, COMPAKTED. NO FILL SHALL BE PLACED BENEATH THE STONE. BEDDING MUST EXTEND EIGHTEEN INCHES MINIMUM PAST THE CISTERN.
7. ROUNDED PEA STONE SHALL BE 1/8" TO 3/8". SUPPLIER SHALL CERTIFY THAT THE MATERIAL MEETS ASTM C-33 SPECIFICATIONS.
8. TANK CAPACITY ABOVE ANTIVORTEX PLATE SHALL BE 30,000 GALLONS MINIMUM.
9. ALL FLANGES SHALL CONFORM TO ANSI B16.5 150 LBS BOLTING PATTERN.
10. TANK INSTALLATION SHALL MEET ALL MANUFACTURER'S GUIDELINES AND RECOMMENDATIONS.
11. EXCAVATION FOR THE TANK SHALL MEET ALL RELAVENT OSHA REQUIREMENTS. DETAILS SHOW ONLY MINIMUM REQUIREMENTS FOR TANK PLACEMENT. NO RECOMMENDATION FOR SIDESLOPES IS IMPLIED.
12. ANTI VORTEX PLATE TO BE INSTALLED BY TANK MANUFACTURER TO XERXES MOST RECENT STANDARDS.
13. THE MANWAY EXTENSION AND COVER SHALL BE CONSTRUCTED OF FIBERGLASS AND SUPPLIED BY TANK MANUFACTURER.
14. ASSUMING GROUNDWATER AT FINAL GRADE:

WGT OF TANK = 9,400# TANK
WET SOIL ABOVE TANK = 2.0'x10'x55.8" (120-62.4)PCF = 64,281# DOWN
SOIL ABOVE TANK CURVE = 9.75Fx55.8" (120-62.4)PCF = 31,176# DOWN
SOIL ABOVE DEADMAN = 2x2x54x11.5" (120-62.4)PCF = 143,078# DOWN
DEADMAN WEIGHT = 2'x1.5'x108" (150-62.4)PCF = 28,382# DOWN
TOTAL DOWN FORCE = DEADMAN + TANK + SOIL = 276,317# DOWN
UPFORCE = 30,590 GAL x 8.34 #/GAL = 255,120# UP
NET FORCE = 21,197# DOWN

15. THE TOWN OF CHESTER HAS A ZERO ALLOWABLE 2 WEEK LEAKAGE TEST AND REQUIRES 1,000 GALLONS PER MINUTE FLOW TEST. THE LEAKAGE TEST WILL BE MONITORED BY THE TOWN'S CONSULTING ENGINEER, AND THE FLOW TEST WILL BE PERFORMED BY THE CHESTER FIRE DEPARTMENT.
16. THE CONTRACTOR SHALL FILL THE TANK BEFORE AND AFTER THE FLOW TEST.
17. THE CISTERN SHALL BE WARRANTED FOR A MINIMUM OF TWO (2) YEARS FROM THE MANUFACTURER. A COPY OF THE WARRANTY WILL BE PROVIDED TO THE FIRE DEPARTMENT.
18. THE CONTRACTOR SHALL PROVIDE A DOCUMENTATION (CUT SHEET) THAT THE CISTERN CONFORMS TO UL-13-16.
19. ALL SUBMITTAL AND DESIGN REQUIREMENTS SHALL CONFORM TO SECTION 9.14 OF THE TOWN OF CHESTER SUBDIVISION REGULATIONS, INCLUDING: REQUIRING SHOP DRAWINGS BE PROVIDED TO THE TOWN FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION OF TANK, ALSO ALL HORIZONTAL PIPING MUST BE PITCHED BACK TO THE TANK AT A SLOPE OF 2%.
20. THE CONTRACTOR SHALL INSTALL A NO PARKING SIGN ON EACH END OF THE TRUCK APRON TO INDICATE NO PARKING IN TRUCK PULL OFF.




The Dubay Group, Inc.
136 Harvey Rd. Bldg B101
Londonderry, NH 03053
603-458-6462

Engineers
Planners
Surveyors
TheDubayGroup.com



40 0 20 40
1 INCH = 40 FEET



REVISIONS:

REV: DATE: COMMENT: BY:

DRAWN BY: JUG
CHECKED BY: DGM
DATE: DECEMBER 17, 2025
SCALE: 1"=40'
FILE: 738-TRUCK TURNING
DEED REF: 5800-2566

PROJECT:
TANGLEWOOD
CANDIA TAX MAP 414
LOTS 152 & 152-10
CHESTER TAX MAP 11
LOTS 30 & 30-7
CROWLEY ROAD
CANDIA & CHESTER NH
FOR/OWNER

DAR BUILDERS, LLC
722 E. INDUSTRIAL
PARK DRIVE
UNIT 17
MANCHESTER, NH 03109

SHEET TITLE:

**TRUCK TURNING
PLAN**

PROJECT #738 SHEET T1

